



6915 SW Macadam Avenue, Suite 200, Portland, OR 97219
Phone: 503-892-1188 FAX: 503-892-1190

Ainsworth Elementary Gym HVAC Replacement and Footing Repairs Portland, OR.

Date: October 23, 2018

Addendum

PLEASE ATTACH TO SPECIFICATION BOOK AND/OR DRAWINGS

Note: The work provided for in this addendum shall become a part of the drawings and specifications for this project.

MECHANICAL DRAWINGS

Sheet MD201

1. **REVISE** keyed note 3 to read, "3. Disconnect and remove (E) steam and condensate, controls, and appurtenances. (E) metal shroud and fan to be abandoned in place."

Sheet M100

1. **ADD** note: "HVAC Controls Note: HVAC controls for new equipment is to be provided by Delta. Connects under a separate contract with the District. Coordinate controls work with controls contractor. Contact information: Michael Campbell, Delta Connects. Phone: 971-266-5642."

Sheet M201

1. Refer to drawing. **REVISE** supply duct routing, show supply grille tap to come off bottom of duct. Show thermostat. **ADD** keyed note 6.
2. **ADD** keyed note 6: "6. Refer to HVAC controls note, Sheet M100."
3. At Lunch Room 16, **REVISE** gas pipe callout to read, "3/4" G (2 psig) in concealed ceiling space."

Sheet M202

1. Refer to drawing. Show thermostat. **ADD** keyed note 5.
2. **ADD** keyed note 5 to read, "5. Refer to HVAC controls note, Sheet M100."

ELECTRICAL DRAWINGS

Sheet E100

1. Refer to drawing. **DELETE** relocation of two (2) sheet metal mounted luminaires. Note relocation of two (2) ceiling surface mount luminaires. **REVISE** keyed note 11 to read, "11. Remove T100 (2) existing surface luminaires to avoid (N) ductwork and equipment. Re-install and extend conduit/conductors as required."

End of Addendum